MYSORE CITY IMPROVEMENT TRUST BOARD.

Dated 8—9th July 1916.

Notice is hereby given that sealed tenders will be received at the office of the Chairman, City Improvement Trust Board Division, up to 28th July 1916, for draining the marsh below Kukkarhalli tank, Mysore. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1917.

2. The plans, detailed estimate and conditions may be seen at the Chairman's Office at Town Hall, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Chairman. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of rupees one hundred and fifty in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for draining the marsh below Kukkarhalli tank," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Chairman, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Chairman's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Items of work.	*Quantity.*
1. Earthwork cutting...	Yds. 22,347
2. Do for carting and filling up the low portion pits with an average of ...	4 furlongs, 15,990 Cq. yds.
3. Surplus earth carting and spreading to level with an average of	4 furlongs, 6,357 Cq. yds.
4. Constructing rough stone jelly drain, (4′ × 3′) ...	1,404 Cq. yds.
5. Turfing on top of drain	126 squares.
6. Removing and reconstructing the stone steps of bathing and washing ponds	Lump sum.
7. Removal of weeds and gass in the bed ...	Do

T. G. LAKSHMANA RAO,
Chairman.

HASSAN DIVISION.

Dated 5th July 1916.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Hassan Division, up to 31st July 1916, for "constructing a bridge across the Sankathirtha river, Alur Sub-Taluk." An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of May 1918.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office at Hassan between the hours of 12 noon and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. (500) five hundred in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for constructing a bridge across the Sankathirtha river, Alur Sub-Taluk," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Chief Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Statement showing the approximate quantities of work for constructing a bridge across the Shankatirtha river, in Alur Sub-Taluk, Hassan District.

Items of work	Per	Quantity
Bridge.		
Excavation in mixed soil with boulders, etc.	C. yd.	1,391
Rock cutting	"	200
Baling out water and unforeseen charges	Lump sum	
Removing boulders from bed	Lump sum	
Concrete in surki mortar filling haunches	C. ft.	2,885
Size stone in surki mortar	"	22,051
Centring of arches	Lump sum	
Stone in surki mortar, faces dressed, arch work	C. ft.	5,125
Stone slab 6" thick set in mortar	S. ft.	1,696
Pointing with surki mortar	Sq.	1417·0
Stone cornice work, plain	R. ft.	342
Earthwork filling (excavated earth)	C. yd.	64
Metalling roadway over bridge, with burnt metal, gravel blindage, sanding, etc., complete	"	43
Year and date stone	Lump sum	
Approach road.		
Diverting cart-track and forming road, etc.	Lump sum	
Compensation for land	Lump sum	
Embankment on either side	Lump sum	

Dated 8th July 1916.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Hassan Division, up to 31st July 1916 for constructing Police Station and lines at Kundur, Alur Sub-taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1917.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office at Hassan between the hours of 12 noon and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed :—

4 Each tender must be accompanied by a deposit of Rs. 200 in cash or Government promissory Notes, as earnest money, and be superscribed "Tender for constructing Police Station and lines at Kundur," Alur Sub-Taluk, in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond: in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the succesful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Statement showing approximate quantities of work for constructing Police Station and lines at Kundur, Alur Sub-Taluk, Hassan District.

Items of work	Per	Quantity for Police Station	Quantities for the Police lines
Earthwork excavation foundation and filling in basement	Cyd.	47	80
Concrete in mortar	C. ft.	205	286
Stone in clay filling foundation	,,	1025	1749
Burnt stone in mortar, basement	,,	579	635
Burnt brick in mortar	,,	441	871
Burnt brick in clay	,,	1815	2379
Burnt stone slabs, 6" thick	S. ft.	199	406
Honney wood work wrought and put up with wood oiling	C. ft.	49·00	110·20
Teakwood battened doors with frame etc. complete	S. ft.	88	439
Teakwood battened windows with frame etc. complete	,,	35	44
Teakwood battened ventilators	,,	11	19
Roofing with Mangalore tiles on teak reepers	Sqr.	11·04	21·15
Ridge tiles	Rft.	40	59
Ceiling with ½" planks (teak) and filling	S. ft.	210	.....
Flooring with 3" concrete and chunam plastering	Sqr.	577	11·85
Gravelling the compound	Cyd.	12	11
Burnt stone pillars with grooves cut	S. ft.	23	.....
Chunam plastering	Sqr.	39·00	71·50
Chunam pointing	,,	412	.....
White and colorwashing	,,	39·00	71·50
Chacolate painting	,,	5·82	14·72
Constructing V.-shaped drain including pointing to slab joints ...	Rft.	80	.....
Teakwood ornamental railings as per plan	,,	52	.....
Teakwood gate with painting	S. ft.	16	.....
Teakwood lock-up doors as per tipe plan	S. ft.	49	.....
Clearing site and levelling ground	Lump sum	.....	Lump sum
Tarring wood work, latrine wall, etc.	,,	.....	do
Fixing drain pipes, flooring latrine seat, etc.	,,	.....	.....
Brick in chunam coping	R. ft.	67	187
Chunam borders	,,	48	61
Teakwood eave board	,,	.....	207
Providing drain pipes 1½"	No.	.....	10
Constructing seats in latrine	,,	.....	Lump sum
Smoke escapes	,,	.....	5
Concrete drain with cement plastering	R. ft.	.....	202

Dated 8th July 1916.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Hassan Division, up to 31st July 1916, for constructing quarters for the Munsiff at Hole-Narsipur. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of January 1917.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office at Hassan, between the hours of 12 noon and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 250 in cash or Government promissory Notes, as earnest money, and be superscribed "Tender for constructing quarters for the Munsiff at Hole-Narsipur;" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one the tenders, the earnest money on rejected tenders will be returned.

Statement showing the approximate quantities of work for constructing Munsiff's Quarters at Hole-Narsipur, Hassan District.

No.	Items of work	Per	Quantities			
			Main building	Kitchen	Stable	Latrine
1	Earthwork excavation for foundation and filling in basement	Cyds.	128	42	27	3
2	Concrete in mortar, filling foundation	Cft.	804	...	...	...
3	Stone in mortar filling foundation	,,	30·02	...	...	...
4	Burnt brick in clay Superstructure	,,	29·79	16·97	10·99	177
5	Do in mortar do	,,	870	435	213	...
6	Do do archwork	,,	118	...	...	...
7	Burnt stone slabs, one line dressed 4" to 6" thick	Sft.	550	278	111	2
8	Burnt stone slab pillars with one line dressed and cutting groves at top for bressummer to rest.	each	2	2	...	...
9	Cast iron pipe pillar 4" Dia. with base and capitals, etc., complete.	,,	2	...	...	...
10	Burnt brick in chunam cornice work with plastering, etc., complete.	Rft.	66	...	..	...
11	Burnt brick in chunam, parapet wall with chunam plastering, etc., complete.	,,	56	...	...	...
12	Plastering with chunam	Sqr.	78·83	41·80	25·29	5·33
13	White and colorwashing	,,	78·83	41·20	25·29	...
14	Teakwood work wrought, and put up with wood oiling, etc., complete.	Cft.	118·80	40·70	29·72	...
15	Pukka terrace roof, complete	Sqr.	1·03	...	...	...
16	Roofing with 1st class Mangalore tiles, with teak reepers, etc., complete.	,,	16·75	11·44	8·08	...
17	Ornamental ridge tiles set in mortar	Rft.	87	43	39	...
18	Teakwood plank ½" thick for valleys	Sft.	316	...	...	...
19	Zinc sheets for valleys	Rft.	158	...	...	...
20	Chunam borders over gable	,,	106	46	...	...
21	Teakwood pannelled doors with iron clamps and iron works etc., complete.	Sft.	196	...	...	...
22	Teakwood battened doors with clamps and iron works etc., complete.	,,	121	170	18	...
23	Teakwood windows, outside panelled and insized glazed shutters, 4 pieces with iron bars, iron work, etc., complete.	,,	188	...	...	...
24	Teakwood glazed ventilators with iron bar, iron work, etc., complete.	,,	54	...	...	...
25	Teakwood glazed circular Ventilators with iron work, etc., complete.	,,	13	...	...	...
26	Teakwood partitions with doorway and iron work etc., complete.	,,	42	...	...	...
27	Chocolate painting to doors windows etc.	Sqr.	19·00	5·88	2·40	...
28	Teakwood ornamental eave board (9")	Rft.	271	138	...	...
29	Teakwood large board complete	Sft.	10	...	...	...
30	Teakwood pendents with painting	Each	16	4	4	...
31	String course or mouldings, top of windows	Rft.	120	...	...	...
32	Teakwood finials with painting	Each	5	2	2	...
33	Plain mouldings at bottom of windows with plastering, etc., complete.	L. S.	...	...	...	...
34	Flooring with Kadappa slabs over 3" concrete bed and cement pointing complete.	Sqr.	2·71	4·06	0·96	0·67
35	Flooring with Mangalore tiles over 3" concrete bed and cement pointing complete.	,,	11·00	1·50	..	...
36	Rain water down pipes with zinc 3" Dia.	Rft.	112	...	...	...
37	Tarring to wood work etc.	L. S.	...	...	...	...
38	Stone in clay filling foundation and basement	Cft.	...	169	884	183
39	Burnt brick in chunam coping with chunam plastering, etc., complete.	Rft.	...	24	...	40
40	Chunam pointing to basement	Sqr.	...	3·09	1·55	...
41	Teakwood battened windows with iron bars and iron work, etc., complete.	Sft.	...	121	12	...
42	Constructing cisterns in bath and kitchen with cement plastering etc., complete.	L. S.	...	...	...	...
43	Providing mortar and pestals for kitchen and raw stone also (2' × 1½').	L. S.	...	...	...	...
44	Constructing chimneys for bath and kitchen	each	...	2	...	...
45	Gravel flooring	L. S.	...	...	...	...
46	Clearing site and levelling ground	L. S.	...	...	...	...
47	Teakwood ordinary eave board	Rft.	...	...	119	...
48	Teakwood door with 2" × 1" thick reepers 2" apart for carriage godown fitted with iron work, iron clamps, etc., complete.	Sft.	...	...	72	...
49	Teakwood battened ventilators with iron bars, iron work, etc., complete.	,,	...	...	18	...
50	Constructing drain to lead off water from main block and providing drainage pipes wherever necessary.	L. S.	...	...	...	...
51	Sinking a well	L. S.	...	...	...	...

K. R. SESHACHAR,
Executive Engineer.